

PLANT SCHEDULE

TREES	QTY	BOTANICAL NAME	COMMON NAME	CONT	CAL	SIZE
	4	BURSERA SIMARUBA	GUMBO LIMBO	B & B	4"CAL	12' HT., 7' SPRD.
	8	COCCOLOBA DIVERSIFOLIA	PIGEON PLUM	B & B	3"CAL	12-14'X6-8'
	15	CONOCARPUS ERECTUS SERICEUS	SILVER BUTTON WOOD	25 GAL		10'-12'H X 5'-6'W
	12	CORDIA SEBESTENA	ORANGE GEIGER TREE	25 GAL	2.5"CAL	8'-9'H X 3'-4'W
	30	LEUCOTHRINAX MORRISII	KEY THATCH PALM	25 GAL		5'HT., FULL
	3	MAGNOLIA GRANDIFLORA 'D.D. BLANCHARD' TM	SOUTHERN MAGNOLIA	B & B	4"CAL	14-16' X 5-7'
SHRUBS	**QTY**	**BOTANICAL NAME**	**COMMON NAME**	**CONT**	**SPACING**	**SIZE**
	9	CAPPARIS CYNOPHALLOPHORA	JAMAICA CAPER	15 GAL	AS SHOWN	42" HT., 28" SPRD.
	83	CHRYSOBALANUS ICACO	COCOPLUM	3 GAL	24" OC	30"X20"
	75	CHRYSOBALANUS ICACO 'HORIZONTALIS'	HORIZONTAL COCOPLUM	3 GAL	24" OC	8"X12"
	44	CLUSIA ROSEA 'NANA'	DWARF PITCH APPLE	3 GAL		14"X12"
	117	MUHLENBERGIA CAPILLARIS	PINK MUHLY	3 GAL	24" OC	24"X24"
	24	PSYCHOTRIA NERVOSA	WILD COFFEE	3 GAL		20"X16"
	161	VIBURNUM OBOVATUM 'DWARF WALTER'S'	DWF. WALTERS VIBURNUM	3 GAL		14"X12"
	78	ZAMIA FLORIDANA	COONTIE PALM	3 GAL	30" O.C.	24"X24"
GROUND COVERS	**QTY**	**BOTANICAL NAME**	**COMMON NAME**	**CONT**	**SPACING**	**SIZE**
	4,974 SF	PASPALUM NOTATUM	BAHIA GRASS	S.F.	TIGHT, FITTED JOINTS	SOD
	7,606 SF	PINE STRAW	PINE STRAW	S.F.	TOTAL BED AREA	2" LAYER
	5,578	STENOTAPHRUM SECUNDATUM 'FLORATAM'	ST. AUGUSTINE SOD	SOD	12" OC	


GUMBO LIMBO TREE


PIGEON PLUM


SILVER BUTTONWOOD


ORANGE GEIGER


KEYS THATCH PALM


MAGNOLIA


JAMAICA CAPER


RED TIP COCOPLUM


PITCH APPLE


PINK MUHLY GRASS


WILD COFFEE


DWARF WALTER'S VIBURNUM


COONTIE PALM

Michael Flaugh
LANDSCAPE ARCHITECT
305.771.6846
isla morada
772.419.0024
Stuart
Houzz.com/pro/MichaelFlaugh www.MikeFlaughLA.com
Fl. Reg. #LA0001728

Sheet
2 of 3
Landscape plan

Preliminary Landscape Plan
SHEPARD PARK
600 SW OCEAN BLVD, STUART, FL 34994

Please note:
The landscape plan is a professional interpretation of existing and proposed site elements based on multiple sources of information. These sources may include: property survey, architectural plans, google aerial imagery, site observations, photographs and site plans. All times, these supporting documents are inaccurate or approximate at best and on-site adjustments to the design during installation are necessary. ***It is the contractors responsibility to verify all measurements and quantities prior to commencing work.***

Date: 11/07/2018
Drawn by: MF
Reviewed by: MF
Scale: 1"=16'
Revised:11/29/2018